



City of Lindsay

DEPARTMENT OF CITY SERVICES

P.O. Box 369 — Lindsay, California 93247 — 150 North Mirage Ave.
559 • 562 • 7102 Option 4
559 • 562 • 5748 fax



September 20, 2023

Water Treatment Plant - Bank D: Media Change-Out Project

Addendum/Clarification No. 1

The following additions and/or corrections shall become part of the Specifications for the subject project:

1. Media Specifications & Quantities:

- a. Below are the media specifications, media quantities, and general information about the media that will be needed for the above-mentioned project:
 - i. 5" 1½" x 3/4"
 - ii. 4" 3/4" x 3/8"
 - iii. 3" 3/8" x 1/4"
 - iv. 3" #6 x #12
 - v. 22" 0.45 – 0.55 < 1.4 uc Sand
 - vi. 12" 0.90 – 1.0 < 1.4 Cuc Anthracite

- b. Media material shall be tested and submitted for City review and approval prior to delivery of product. All filter media tested shall meet or exceed AWWA B100-19 specifications.

2. Vessel Dimensions

- a. Below are the dimensions for the vessel:
 - i. 16' H x 12' Dia.

3. Vessels shall be blasted to near white per NACE No. 2/SSPC-SP10

4. Polibrid 705E Elastomeric Polyurethane will be accepted as an **approved equal** to Endura-Flex Elastomeric Polyurethane.

This completes the items included in this Addendum/Clarification No. 1 for the City of Lindsay, **Water Treatment Plant - Bank D: Media Change-Out Project**. This Addendum cover page shall be signed and submitted with bid proposal.

Contractor

Date

